



- Notes
- Existing tree to be removed, including stump. Trunk to be retained and delivered to Parish Council.
 - New concrete gully to be installed.
 - Existing kerb line to be removed to tip off site.
 - Line marking to the relevant diagram no. of the TSRGD 2016.
 - Existing bollard to be removed to tip off site.
 - Post and rail timber fence installed to manufacturer's specification.
 - Remove all existing planting and highway furniture. Reinststate these areas with top soil and grass seed
 - Excavate existing carriageway and replace with top soil to meet existing footway/green level and grass seed.
 - Excavate existing village green and reinststate carriageway.
 - Proposed installation of Ketley Staffordshire Blue Diamond Chequered clay paver.
 - Proposed location for new trees to replace loss of existing trees.
 - Proposed new road sign

A	06/06/18	Parking layby width increased to 2.5m. Kerbline revised outside No.2 High Street.	DRB	BB	WB
0	10/05/18	FIRST ISSUE	CCM		
Rev	Revision Date	Purpose of revision	Drawn	Chec'd	App'd



Kent County Council
kent.gov.uk



Kent County Council
Ashford Highway Depot
Henwood Industrial Estate
Ashford
TN24 8AD
Tel: 03000 418181

Project
**HIGH STREET,
BIDDENDEN**

Drawing title
DETAILED DESIGN

Drawing status
FOR CONSTRUCTION

Scale
1:320 @ A3 **Do not scale**

Drawing number
18/19-LTP-AS-536/1101

Rev
A

This drawing is not to be used in whole or part other than for the intended purpose and project as defined on this drawing. Refer to the contract for full terms and conditions.